### Carolina Estates Replat A

City of El Paso — City Plan Commission — 6/14/2018

SUSU17-00040 — Resubdivision Combination

STAFF CONTACT: Vanessa Munoz, (915) 212-1644, munozvx@elpasotexas.gov

PROPERTY OWNER: Ramos and Robles, Inc., d/b/a Sunset Funeral Home

H2O Terra REPRESENTATIVE:

LOCATION: South of Carolina and West of Yarbrough, District 7

1.338 ACREAGE: VESTED: No

PARK FEES REQUIRED: \$1,340.00

EXCEPTION/MODIFICATION

**REQUEST:** 

1. Yes, to waive the required street improvements to the applicant's

proportionate share of Carolina Drive.

**RELATED APPLICATIONS:** PZRZ15-00034

PZST17-00038

PUBLIC INPUT: N/A

STAFF RECOMMENDATION: **PENDING** 

**SUMMARY OF REQUEST:** The applicant proposes to resubdivide 1.338 acres of land for one commercial lot. Currently, there is a funeral home on the subject property and the applicant is proposing a crematorium upon City Council approval of a special permit to allow for a crematorium. Access to the subdivision is from Carolina.

SUMMARY OF RECOMMENDATION: Planning staff's recommendation is PENDING of Carolina Estates Replat A on a resubdivision combination basis, subject to the following outstanding staff comments:

- City Council approval of a special permit to allow for a crematorium and a rezoning application to rezone to C-2.
- Clarification on whether the dedication of 4 feet of additional right-of-way along Carolina will be dedicated in order to comply with DSC requirements for a minor arterial. Currently, there is 35' feet of existing ROW along the applicant's proportionate share, however, Carolina is designated as a minor arterial requiring 78' of right-of-way. As a result, the applicant will need to dedicate 4 additional feet of right-of-way.

Submittal of revised final plat.



### **DESCRIPTION OF ANY EXCEPTIONS, MODIFICATIONS, OR WAIVERS**


The applicant is requesting the following exception under 19.10.050-A.1.a. (Roadway participation policies):

1. To waive the required street improvements to the applicant's proportionate share of Carolina Drive.

### **Carolina Drive**

### Required

The DSC requires a 10' parkway with a 5' landscape buffer, a 5' sidewalk and 22' of pavement as well as a 7' raised turning median.




### MINOR ARTERIAL STREET

FOUR (4) LANES

### **Existing**

The applicant proposes to preserve the existing configuration of Carolina Drive, which includes a 5' sidewalk, 4' parkway and 26' of pavement. As such, the applicant is requesting to waive 1' of parkway and 3' of roadway as required per the DSC. The linear street frontage the proposed subdivision will have along Carolina Drive is approximately 177 feet.



### EXISTING CAROLINA DRIVE CROSS SECTION

SCALE 1" = 10'

Currently, the applicant has the proper configuration of the improvements. The roadway is consistent throughout Carolina within a quarter mile; however, the parkway varies throughout as certain parcels have the sidewalk and no parkway or vice versa.

### RELATION OF PROPOSED APPLICATION TO THE CITY'S COMPREHENSIVE PLAN

CONSISTENCY WITH PLAN EL PASO: Subject property is designated G3, Post-War

### **GOAL 2.1**

The City should change its growth pattern away from continuous outward expansion and toward integrated growth that minimizes environmental change, reduces the need for excessive travel by private automobile, and can be served by public transportation.

### **GOAL 2.2**

The City of El Paso should change its growth pattern away from homogeneous land uses and return to a pattern of compact well-connected mixed-use neighborhoods.

POLICY	DOES IT COMPLY?
<b>2.1.9:</b> Development is strongly discouraged within critical arroyos.	Yes, the applicant is not developing within a critical arroyo.
<b>2.2.4.b.:</b> Commercial and office uses at intersections should have direct paths to greens and squares.	No, the proposed development does not have direct paths to greens and squares.
<b>2.2.6.:</b> The design of new neighborhoods and additions to existing neighborhoods should strive for a balance of housing, jobs, shopping, recreation, and civic uses to avoid unnecessary travel and reduce infrastructure and public services costs.	No, the applicant current land use is for commercial purposes only.

**NEIGHBORHOOD CHARACTER:** Subject property is zoned C-1 and C-2 (Commercial) and is currently occupied by a funeral home. Properties adjacent to the subject property are zoned C-1 (Commercial), R-3 (Residential), and R-F (Ranch Farm). Surrounding land uses are residential and commercial developments. The nearest school is Bel Air High School (0.92 miles). The nearest park is Officer David Ortiz (0.26 miles). This property is not located within any Impact Fee Service Area.

### **COMMENT FROM THE PUBLIC:** N/A.

### **STAFF COMMENTS:**

Planning staff's recommendation is **PENDING** of Carolina Estates Replat A on a resubdivision combination basis, subject to the following outstanding staff comments:


- City Council approval of a special permit to allow for a crematorium and a rezoning application to rezone to C-2.
- Clarification on whether the dedication of 4 feet of additional right-of-way along Carolina will be dedicated in order to comply with DSC requirements for a minor arterial. Currently, there is 35' feet of existing ROW along the applicant's proportionate share, however, Carolina is designated as a minor arterial requiring 78' of right-of-way. As a result, the applicant will need to dedicate 4 additional feet of right-of-way.
- Submittal of revised final plat.


### **PLAT EXPIRATION:**


This application will expire on <u>June 14, 2021</u>, pursuant to Section 19.03.060 (Expiration). If subdivision improvement plans and a final plat application have not been approved within the specified date, the preliminary plat application, unless extended in accordance with Chapter 19.41 (Expiration, extension and reinstatement), shall expire and the preliminary plat shall be null and void.

### **ATTACHMENTS:**

- 1. Location Map
- 2. Preliminary plat
- 3. Final Plat
- 4. Exception Request
- 5. Application
- 6. Department Comments









CIVIL ENGINEERING PLANNING LAND DEVELOPMENT SURVEYING WATER WASTEWATER

2020 E. Mills Ave. | El Paso, TX 79901 | P (915) 533-1418 | F (915) 533-4972 | H2O-Terra.com

03/28/2018

City of El Paso, Planning and Inspections Rocio Alvarado, Planner City 3 801 Texas Avenue El Paso, Texas 79901

Re: CAROLINA ESTATES REPLAT "A" (RIGHT-OF-WAY IMPROVEMENT WAIVER)

Dear Ms. Alvarado,

We are respectfully asking for a Right-of-way Improvement Waiver as per Section 19.10.050A.1.a.

Carolina Drive has an existing right-of-way width of 70 feet. The street section at the front of this parcel has a 70-foot-wide right-of-way, with an existing pavement width of 52.0 feet at the cross section taken, a 5.0-foot sidewalk adjacent to the right-of-way line and a 4-foot parkway adjacent to the curb on our side of the street and a 3.5 foot parkway adjacent to the right-of-way line and a 5.5 foot sidewalk adjacent to the curb on the opposite side of the street. Please see attached cross section. This street section exists for several hundred feet.

If you have any questions regarding this matter, please do not hesitate to call.

Sincerely,

Jose Hernandez, P.E. H2O Terra

JHernandez@H2O-Terrra.com



## CITY PLAN COMMISSION APPLICATION FOR RESUBDIVISION COMBINATION SUBDIVISION APPROVAL

	or the area included on this OF LOT 1, BLOCK 1, CAR CITY OF EL PASO, EL PAS	plat (Tract, Block, Grant, etc.) DLINA ESTATES AND ALL OF TRACT 2B3A, BLOCK 18,
TSLETA GRANT,	DITY OF EL PASO, EL PAS	O COUNTY, TEXAS
Property Land Uses	: ACRES SITI	ES ACRES SITE
Single-family		Office
Duplex		Street & Alley
Apartment		
Mobile Home P.U.D.		Institutional Other (specify below)
Park		Other (specify delow)
School		1.338
Commercial	1.338 1	Total 140. Dites
Industrial		Total (Gross) Acreage 1.338
What is existing zo	ning of the above described	d property? C-1 / C-2 Proposed zoning? C-1 / C-2
	sites, as proposed, permit zone(s)? Yes_X	development in full compliance with all zoning requirements of No
What type of utility	easements are proposed:	Underground Overhead Combination of Both_X_
What type of drains Surface to exisitng	ge is proposed? (If applic drainage pond	able, list more than one)
	mprovements proposed in	connection with development? Yes No X
Are special public		
Is a modification or	exception of any portion of please explain the nature of	of the Subdivision Ordinance proposed? Yes X No_ f the modification or exception Scale of 1" = 30" on plat for ease
Is a modification or If answer is "Yes", of presentation	please explain the nature of	of the Subdivision Ordinance proposed? Yes X No_ f the modification or exception_Scale of 1" = 30" on plat for ease stances:

City Development Department 811 Texas | P.O. Box 1890 | El Paso, Texas 79950-1890 | (915) 212-0085

RAMOS AND ROBLES, INC., DBA SUNSET FUNERAL HOMES, JOE RAMOS, PRESIDENT

12. Owner of record 750 CAROLINA DRIVE, EL PASO, TEXAS 79915, (915) 858-4408

(Name & Address) (Zip) (Phone)

13. Developer SAME AS ABOVE

(Name & Address)

H20 TERRA, JOSE HERNANDEZ, P.E., 2020 E. MILLS AVENUE, EL PASO, TEXAS 79901,

14. Engineer OFFICE: (915) 533 - 1418, FAX: (915) 533 - 4972

(Name & Address)

\*Effective September 1, 2014, a 3% technology fee has been added to all Planning application fees.

REPRESENTATIVE: REPRESENTATIVE: PASO, TEXAS 79901,

\*EFFRESENTATIVE: PASO, TEXAS 79901,

REPRESENTATIVE: PASO, TEXAS 79901,

(Phone)

NOTE: SUBMITTAL OF AN APPLICATION DOES NOT CONSTITUTE ACCEPTANCE FOR PROCESSING UNTIL THE PLANNING DEPARTMENT REVIEWS THE APPLICATION FOR ACCURACY AND COMPLETENESS.

City Development Department 811 Texas | P.O. Box 1890 | El Paso, Texas 79950-1890| (915) 212-0085

### PLANNING AND INSPECTION DEPARTMENT - PLANNING:

Developer / Engineer shall address the following comments:

- 1: Submit to the Planning & Inspections Department Planning Division the following prior to recording of the subdivision:
  - a: Current certificate tax certificate(s)
  - b: Current proof of ownership.
  - c: Release of access document, if applicable.
  - d: Set of restrictive covenants, if applicable.
- 2: Every subdivision shall provide for postal delivery service. The subdivider shall coordinate the installation and construction with the United States Postal Service in determining the type of delivery service for the proposed subdivision. In all cases, the type and location of delivery service shall be subject to the approval of the United States Postal Service.

### PLANNING AND INSPECTION DEPARTMENT - LAND DEVELOPMENT:

We have reviewed subject plats and recommend Approval. The Developer/Engineer shall address the following comments.

- 1. Show existing and proposed drainage flow patterns on the preliminary plat. Identify the discharge location for all storm-water runoff.
- 2. Need to show the storm sewer lines along Carolina Dr. in front of the property.
- 3. Dimensions driveway widths.
- 4. Add FEMA flood zone information to general notes on both preliminary and final plats.

### **CAPITAL IMPROVEMENTS DEPARTMENT - PARKS:**

We have reviewed <u>Carolina Estates Replat "A"</u>, a resubdivision combination plat map and on behalf of CID Parks & Planning Division we offer Developer / Engineer the following comments:

Please note that this subdivision is zoned "C-1 & C-2" meeting the requirements for Non-residential uses (General commercial) as well as for Multi-family dwellings use (Apartments) restricted to a maximum of 29 dwelling units per acre however, applicant has submitted copy of preliminary covenants restricting the use to Non-residential (General commercial) therefore, "Park fees" will be assessed as follows:

If applicant provides copy of final signed/recorded covenants restricting the use to Non-residential (General commercial) and if gross density waiver is granted by the City Manager or the Planning Department designee, then Applicant shall be required to pay "Park fees" in the amount of \$1,340.00 based on Non-residential subdivision requirements calculated as follows:

Non-residential acreage 1.338 (rounded to 2 decimals) @ \$1,000.00/acre = \$1,340.00

Please allocate generated funds under Park Zone: MV-1

Nearest Park: Carolina Park

**If** density/acreage is increased /decreased or the property zoning /use changes, then "Park fees" will be re-assessed based on applicable conditions.

### **EL PASO WATER:**

EPWater-PSB does not object to this request.

### Water:

There is an existing 6-inch diameter water main that extends along the north side of Carolina Dr., approximately 15-feet north of and parallel to the northern curb and gutter line of Carolina Dr. This water main is available for service.

EPWater records indicate there is an active 1-inch water meter serving the subject property. The service address for this meter is 740 N. Carolina Dr.

Previous water pressure from fire hydrant #3117 located at the northwest corner of Giles Rd. and Carolina Dr. has yield a static pressure of 90 psi, a residual pressure of 78 psi, and a discharge flow of 750 gallons per minute.

The owner should, for his own protection and at his own expense, install a pressure regulator, strainer and relief valve at the discharge side of each water meter to be set at a pressure desired by the customer. The Lot owner shall be responsible for the operation and maintenance of the above-described water pressure regulating device.

#### Sewer:

There is an existing 8-inch diameter sanitary sewer main that extends along the north side of Carolina Dr., approximately 5-feet north of and parallel to the northern curb and gutter line of Carolina Dr. This sanitary sewer main is available for service.

There is an existing 12-inch diameter sanitary sewer main that extends along the 10-foot PSB Easement, North of Bowman Lateral. This sanitary sewer main is available for service.

#### General:

No building, reservoir, structure, parking stalls or other improvement, other than asphaltic paving (HMAC), shall be constructed or maintained on the above referenced EPWU-PSB easement without the written consent of EPWU-PSB. The Developer shall refrain from constructing rock walls, signs, buildings, curbs or any structure that will interfere with the access to the PSB easements. There shall be at least 5-foot setback from the easement line to any building, sign or structure. All easements dedicated for public water and sanitary sewer facilities shall comply with the EPWU-PSB Easement Policy. The PSB easements shall be improved to allow the operation of EPWU maintenance vehicles. EPWU-PSB requires access to the proposed water, sanitary sewer facilities, appurtenances, and meters within the easement 24 hours a day, seven (7) days a week.

EPWater requires a new service application for additional services to the subject property. New service applications are available at 1154 Hawkins, 3rd Floor. The following items are required at the time of application: (1) hard copy of subdivision plat with street names and addresses; (2) finalized set of improvement plans, including storm sewer; (3) digital copy of subdivision plat; (4) benchmark check; and (5) construction schedule. Service will be provided in accordance with the current EPWater – PSB Rules and Regulations. The owner is responsible for the costs of any necessary on-site and off-site extensions, relocations or adjustments of water and sanitary sewer lines and appurtenances.

### El Paso Electric:

Easement shown is sufficient.

### El Paso County Water Improvement District:

No comments received.